

RESOLUTION NO. 36-14
CITY OF CENTERVILLE, OHIO

SPONSORED BY COUNCILMEMBER John Beards ON
THE 15th DAY OF September, 2014.

A RESOLUTION ACCEPTING THE BID
SUBMITTED BY BRUMBAUGH
CONSTRUCTION, INC. OF ARCANUM, OHIO
FOR THE NORTH VILLAGE ACCESS DRIVE
AT WOODBOURNE LIBRARY (PROJECT SS-
13), IN THE CITY OF CENTERVILLE AND
AUTHORIZING THE CITY MANAGER TO
ENTER INTO A CONTRACT IN CONNECTION
THEREWITH.

WHEREAS, the City of Centerville and the Washington-Centerville Public Library had previously entered into a Joint Project agreement dated September 3, 2013 for the Woodbourne Library Egress Drive Project, whereby the City of Centerville agreed to manage the Project and contribute an amount not to exceed \$50,000; and

WHEREAS, as the Manager of the Project, the City of Centerville agreed to coordinate and bid the Project in cooperation with the requests of the Library; and

WHEREAS, the City has agreed that while the City may authorize the City Manager to expend funds for the Project and execute contracts necessary for the Project, it is understood that the City's costs are not to exceed the \$50,000 cap and any additional expenditures are the responsibility of the Library and any alternate bid approvals are based upon the Library's requests and consent; and

WHEREAS, the City of Centerville advertised for bids for the North Village Access Drive at Woodbourne Library according to specifications prepared by the City; and

WHEREAS, Brumbaugh Construction, Inc, of Arcanum, Ohio, was the low and best bidder.


NOW, THEREFORE, THE MUNICIPALITY OF CENTERVILLE
HEREBY RESOLVES:

Section 1. That the base bid and Alternate 1 submitted by Brumbaugh Construction, Inc. of Arcanum, Ohio for the North Village Access Drive at Woodbourne Library (Project SS-13), is hereby accepted in the amount of \$426,399. The City Manager is hereby authorized to expend up to an additional \$25,000 for additional work if necessary and requested by the Library, making the total amount approved \$451,399, a copy of which is attached hereto, incorporated herein and marked as Exhibit "A". The City's share is to be capped at \$50,000.

Section 2. That the City Manager is hereby authorized to do all things necessary to execute a contract with Brumbaugh Construction, Inc., as stated above.

Section 3. This resolution shall become effective at the earliest date allowed by law.

PASSED this 15th day of September, 2014.



Mayor, City of Centerville, Ohio


ATTEST:



Clerk of Council, City of Centerville, Ohio

CERTIFICATE

The undersigned, Clerk of the Council of the City of Centerville, Ohio hereby certifies that the foregoing is a true and correct copy of Resolution Number 36-14 passed by the Council of the City of Centerville, Ohio on the 15th day of September, 2014.



Clerk of Council

Approved as to form, consistency
with existing ordinances, the
Charter and Constitutional Provisions.

Department of Law
Scott A. Liberman
Municipal Attorney

BIDDER'S PROPOSAL

North Village Access Drive at Woodbourne Library

Submitted by: Brumbaugh Construction, Inc.

Having read the specifications and examined the drawings included herein:

**North Village Access Drive at Woodbourne Library
City of Centerville, Ohio**

for the construction of said project in Centerville, Ohio, and having also taken into account all addenda issued, the undersigned hereby propose to furnish all materials and to perform all labor, as specified and described in the said Specifications and as shown in the Plans for the said work, for the following sums:

A. STATEMENT BY ALL BIDDERS:

The receipt of the following Addenda to the Contract Document (drawings and specifications) is hereafter acknowledged.

Addenda No. _____ Date _____

Addenda No. _____ Date _____

Addenda No. _____ Date _____

B. COMPLETION DATE INFORMATION

The bid price reflected above represents a completion date of **May 15, 2015**.

C. CONTRACT PREPARATION INFORMATION

The bidder shall supplement proposal by supplying the following information for use in the preparation of the Contract.

NAME OF COMPANY/CORPORATION: BRUMBAUGH CONSTRUCTION, INC.

NAME OF PRESIDENT: Scott Myers

ADDRESS: 3520 St. Rt. #49, P.O. Box 309

CITY, STATE, ZIP: Arcanum, Ohio 45304

FEDERAL TAX I.D. #: _____

TELEPHONE #: (937)692-5107


FAX #: (937)692-5678

E-MAIL: dan@brumbaughconstruction.com

D. EXECUTION OF PROPOSAL

NOTE: Failure to sign proposal shall result in rejection of bid.

THIS PROPOSAL SUBMITTED BY: BRUMBAUGH CONSTRUCTION, INC.
(NAME OF CONTRACTOR)

BY: 
(SIGNATURE OF CONTRACTOR OR AUTHORIZED REPRESENTATIVE)

Daniel W. Hayes, Assistant Vice President
(PRINTED NAME AND TITLE)

DATE: September 10, 2014

Contact person for Contract processing: Dan Hayes

Mailing address if different from above: P.O. Box 309, Arcanum, Ohio 45304

UNIT PRICE SHEET

PROJECT NAME: North Village Access Drive at Woodbourne Library

PROJECT NUMBER: SS-13

THE CITY OF CENTERVILLE CONSTRUCTION AND MATERIAL SPECIFICATIONS ARE PART OF THIS PROPOSAL AND MAY BE REFERENCED FOR A MORE COMPLETE DESCRIPTION OF THE ITEMS LISTED. RETURN ONE (1) FILLED-IN COPY OF PROPERLY SIGNED PROPOSAL TOGETHER WITH THE EXECUTED FORMS.

REF NUM	SPEC NUM	DESCRIPTION	ESTD QUANT	UNITS	UNIT PRICE	AMOUNT BID
------------	-------------	-------------	---------------	-------	------------	------------

BASE BID

ROADWAY

1	201	CLEARING AND GRUBBING	1	LUMP	15,000.00	15,000.00
2	202	PAVEMENT REMOVED (CONCRETE)	38	SQ YD	65.00	2,470.00
3	202	FENCE REMOVED	35	FT	4.00	140.00
4	202	CURB REMOVED	261	FT	3.00	783.00
5	202	PIPE REMOVED, 24" AND UNDER	9	FT	7.50	67.50
6	203	EXCAVATION	175	CU YD	18.00	3,150.00
7	203	EMBANKMENT	595	CU YD	28.00	16,660.00
8	204	SUBGRADE COMPACTION	418	SQ YD	1.00	418.00
9	204	PROOF ROLLING	1	HOUR	75.00	75.00
10	608	4" CONCRETE WALK (4" AGGREGATE BASE, CRUSHED LIMESTONE, INCLUDED IN COST)	1540	SQ FT	7.00	10,780.00
11	608	8" CONCRETE WALK (6" AGGREGATE BASE, CRUSHED LIMESTONE, INCLUDED IN COST)	84	SQ FT	12.00	1,008.00
12	608	CURB RAMP, AS PER PLAN (6" AGGREGATE BASE, CRUSHED LIMESTONE, INCLUDED IN COST)	1	EACH	1,400.00	1,400.00
13	661	EVERGREEN SHRUB, 12" HEIGHT	12	EACH	140.00	1,680.00
14	661	DECIDUOUS TREE, 2-1/2" CALIPER (MAPLE)	2	EACH	370.00	740.00
15	690	SPECIAL - MISC.: DUMPSTER ENCLOSURE	1	LUMP	17,000.00	17,000.00

EROSION CONTROL

16	653	TOPSOIL FURNISHED AND PLACED	84	CU YD	26.00	2,184.00
17	659	SEEDING AND MULCHING	756	SQ YD	1.70	1,285.20
18	659	REPAIR SEEDING AND MULCHING	38	SQ YD	1.00	38.00
19	659	INTER-SEEDING	38	SQ YD	1.00	38.00
20	659	COMMERCIAL FERTILIZER	0.11	TON	600.00	66.00
21	659	LIME	0.16	ACRE	12.00	1.92
22	659	WATER	4.08	MGAL	5.00	20.40
23	832	EROSION CONTROL	1250	EACH	1.00	1,250.00

DRAINAGE

24	811	4" CONDUIT, TYPE E, 707.32	100	FT	10.00	1,000.00
25	811	6" CONDUIT, TYPE E, 707.32	100	FT	12.00	1,200.00
26	811	12" CONDUIT, TYPE B, 706.02	114	FT	46.00	5,244.00
27	811	24" CONDUIT, TYPE B, 706.02	9	FT	100.00	900.00
28	811	MODIFIED CB-3 CATCH BASIN	1	EACH	4,900.00	4,900.00

PAVEMENT

29	304	AGGREGATE BASE	71	CU YD	45.00	3,195.00
30	407	TACK COAT FOR INTERMEDIATE COURSE	22	GALLON	5.00	110.00
31	408	PRIME COAT	114	GALLON	5.00	570.00
32	448	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22	20	CU YD	300.00	6,000.00
33	448	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22	12	CU YD	325.00	3,900.00
34	452	8" NON-REINFORCED CONCRETE PAVEMENT, CLASS QC1 (6" AGGREGATE BASE, CRUSHED LIMESTONE, INCLUDED IN COST)	17	SQ YD	90.00	1,530.00

REF NUM	SPEC NUM	DESCRIPTION	EST'D QUANT	UNITS	UNIT PRICE	AMOUNT BID
35	609	CURB, TYPE 6 (6" AGGREGATE BASE, CRUSHED LIMESTONE, INCLUDED IN COST)	408	FT	27.00	11,016.00
36	609	CURB, TYPE 7 (6" AGGREGATE BASE, CRUSHED LIMESTONE, INCLUDED IN COST)	31	FT	36.00	1,116.00
SANITARY SEWER						
37	811	MANHOLE RECONSTRUCTED TO GRADE	2	EACH	400.00	800.00
LIGHTING						
38	625	CONDUIT, 1-1/2", 725.05, AS PER PLAN	113	FT	15.00	1,695.00
39	625	TRENCH, 24" DEEP, AS PER PLAN	113	FT	15.00	1,695.00
TRAFFIC CONTROL						
40	630	GROUND MOUNTED SUPPORT	9	FT	11.00	99.00
41	630	SIGN, FLAT SHEET	2.25	SQ FT	23.00	51.75
42	630	SIGNING, MISC.: PRIVATE SIGN REMOVED & RESET	1	EACH	170.00	170.00
43	644	PARKING LOT STALL MARKING	38	FT	20.00	720.00
44	644	LANE ARROW	2	EACH	280.00	560.00
RETAINING WALLS						
45	810	CELLULAR RETAINING WALL, AS PER PLAN	348	SQ FT	50.00	17,450.00
STRUCTURES (20' AND OVER)						
46	503	COFFERDAMS AND EXCAVATION BRACING	1	LUMP	900.00	900.00
47	503	UNCLASSIFIED EXCAVATION	297	CU YD	24.00	7,128.00
48	509	EPOXY COATED REINFORCING STEEL	7848	LB	.80	6,278.40
49	511	CLASS QC1 CONCRETE (RET WALL/WINGWALL, ABOVE FOOTING)	32	CU YD	370.00	11,840.00
50	511	CLASS QC1 CONCRETE, FOOTING	67	CU YD	350.00	23,450.00
51	511	CLASS QC1 CONCRETE, HEADWALL	3	CU YD	1,200.00	3,600.00
52	511	CLASS QC1 CONCRETE, MISC.: FENCE POST FOUNDATION	1	CU YD	2,200.00	2,200.00
53	512	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)	103	SQ YD	23.00	2,369.00
54	512	TYPE 2 WATERPROOFING	114	SQ YD	22.00	2,508.00
55	512	TYPE 3 WATERPROOFING	150	SQ YD	28.00	4,200.00
56	516	1" PREFORMED EXPANSION JOINT FILLER	68	SQ FT	1.50	99.00
57	518	POROUS BACKFILL WITH FILTER FABRIC	38	CU YD	45.00	1,620.00
58	601	ROCK CHANNEL PROTECTION, TYPE C WITH FABRIC FILTER	82	CU YD	60.00	4,920.00
59	607	FENCE, MISC.: WOOD FENCE	80	FT	135.00	8,100.00
60	611	CONDUIT, MISC.: 24' X 8' CONDUIT, TYPE A, 708.05	48	FT	2775.00	133,200.00
MAINTENANCE OF TRAFFIC						
61	616	WATER	2	MGAL	5.00	10.00
62	614	MAINTAINING TRAFFIC	1	LUMP	6,000.00	6,000.00
63	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING	1	LUMP	3302.83	3,302.83
64	624	MOBILIZATION	1	LUMP	7,000.00	7,000.00
TOTAL BASE BID						368,902.00

ALTERNATE 1 - BOOK DROP DRIVE

ROADWAY

65	201	CLEARING AND GRUBBING	1	LUMP	15,000.00	15,000.00
66	202	WALK REMOVED	81	SQ FT	13.00	1,053.00
67	202	CURB REMOVED	5	FT	15.00	75.00
68	202	SPECIAL - PARKING BLOCK REMOVED	5	EACH	27.00	135.00
69	202	REMOVAL MISC.: PICNIC TABLE REMOVED AND RESET	1	LUMP	200.00	200.00
70	203	EXCAVATION	120	CU YD	22.00	2,640.00

REF NUM	SPEC NUM	DESCRIPTION	ESTD QUANT	UNITS	UNIT PRICE	AMOUNT BID
71	203	EMBANKMENT	37	CU YD	28.00	1,036.00
72	204	SUBGRADE COMPACTION	408	SQ YD	1.00	408.00
73	608	4" CONCRETE WALK (4" AGGREGATE BASE, CRUSHED LIMESTONE, INCLUDED IN COST)	23	SQ FT	16.00	368.00
74	608	CURB RAMP (6" AGGREGATE BASE, CRUSHED LIMESTONE, INCLUDED IN COST)	2	EACH	1,400.00	2,800.00
75	690	SPECIAL - BOLLARD	1	EACH	460.00	460.00
EROSION CONTROL						
76	601	CRUSHED AGGREGATE SLOPE PROTECTION	3	SQ YD	105.00	315.00
77	659	TOPSOIL FURNISHED AND PLACED	18	CU YD	30.00	540.00
78	659	SEEDING AND MULCHING	159	SQ YD	3.60	572.40
79	659	REPAIR SEEDING AND MULCHING	8	SQ YD	1.00	8.00
80	659	INTER-SEEDING	8	SQ YD	1.00	8.00
81	659	COMMERCIAL FERTILIZER	0.02	TON	650.00	13.00
82	659	LIME	0.03	ACRE	100.00	3.00
83	659	WATER	0.86	MGAL	5.00	4.30
84	832	EROSION CONTROL	600	EACH	1.00	600.00
PAVEMENT						
85	304	AGGREGATE BASE	93	CU YD	45.00	4,185.00
86	407	TACK COAT FOR INTERMEDIATE COURSE	28	GALLON	5.00	140.00
87	408	PRIME COAT	148	GALLON	5.00	740.00
88	448	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22	26	CU YD	290.00	7,540.00
89	448	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22	18	CU YD	305.00	4,880.00
90	608	CURB, TYPE 6 (6" AGGREGATE BASE, CRUSHED LIMESTONE, INCLUDED IN COST)	254	FT	27.00	6,858.00
TRAFFIC CONTROL						
91	630	GROUND MOUNTED SUPPORT	36	FT	11.00	396.00
92	630	SIGN, FLAT SHEET	9.71	SQ FT	23.00	223.33
93	630	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	1	EACH	20.00	20.00
94	630	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	1	EACH	30.00	30.00
95	644	EDGE LINE, 4"	0.01	MILE	23,100.00	231.00
96	644	TRANSVERSE/DIAGONAL LINE	17	FT	9.00	153.00
97	644	LANE ARROW	1	EACH	165.00	165.00
MISCELLANEOUS						
98	623	CONSTRUCTION LAYOUT STAKES AND SURVEYING	1	LUMP	5,696.97	5,696.97
TOTAL ALTERNATE 1						57,497.00

ALTERNATE 2 - DUMPSTER ENCLOSURE (APPROXIMATE STA. 12+66, 75' RT)

99	690	SPECIAL - MISC.: DUMPSTER ENCLOSURE (NO PAD)	1	LUMP	15,000.00	15,000.00
TOTAL ALTERNATE 2						15,000.00