

RESOLUTION NO. 7-93

CITY OF CENTERVILLE, OHIO

SPONSORED BY COUNCILMEMBER James Singer ON THE
1st DAY OF March, 1993.

A RESOLUTION ACCEPTING THE BID OF PYPER
CONSTRUCTION COMPANY FOR THE CLYO ROAD
EXTENSION PROJECT IN THE CITY OF CENTERVILLE
AND TO AUTHORIZE THE CITY MANAGER TO ENTER
INTO A CONTRACT IN CONNECTION THEREWITH.

WHEREAS, the City advertised for bidders for the
extension of Clyo Road in the City of Centerville, pursuant to
specifications prepared by the City; and


WHEREAS, Pyper Construction Company was the lowest and
best bidder;

NOW, THEREFORE, THE MUNICIPALITY OF CENTERVILLE HEREBY
RESOLVES:

SECTION 1. The bid of Pyper Construction Company
in the amount of \$1,191,748.35, marked Exhibit "A" attached
hereto and made a part hereof is hereby accepted and the City
Manager is hereby authorized and directed to enter into any
necessary contract to evidence acceptance of said bid and to make
payment pursuant thereto.

SECTION 2. This Resolution shall become effective at
the earliest date allowed by law.

1993. PASSED this 1st day of March,



Mayor of the City of
Centerville, Ohio

ATTEST:


Clerk of the Council of the
City of Centerville, Ohio

CERTIFICATE

The undersigned, Clerk of the Council of the City of Centerville, Ohio, hereby certifies that the foregoing is a true and correct copy of Resolution Number 7-93, passed by the Council of the City of Centerville, Ohio, on the 1st day of March, 1993.


Clerk of Council

Approved as to form, consistency
with the Charter and Constitutional Provisions.
Department of Law
Robert N. Farquhar
Municipal Attorney

**CITY OF CENTERVILLE - Clyo Road Extension III
PROJECT DETAIL SHEETS**

Revised February 16, 1993

REF NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
ROADWAY CONSTRUCTION						
1	201	Clearing and Grubbing	LS	1	24,000.00	24,000.00
2	202	Remove Existing Pipe, up to 24"	LF	15	10.00	150.00
3	202	Remove Existing 48" Pipe	LF	3	10.00	30.00
4	202	Remove Existing Curb and Gutter	LF	10	5.00	50.00
5	203	Excavation, not including embankment const.	CY	32,227	2.45	78,956.15
6	203	Embankment	CY	12,463	0.95	11,839.85
7	203	Subgrade Compaction	SY	27,739	0.85	23,578.15
8	301	8.5" Bituminous Aggregate Base	CY	7,239	36.85	266,757.15
9	304	6" Aggregate Base	CY	4,465	19.00	84,835.00
10	304	12" Aggregate Base	CY	308	19.00	5,852.00
11	304	4" Aggregate Base (walks)	CY	604	19.00	11,476.00
12	402	2" Asphalt Concrete, AC-20	CY	1,844	37.69	69,500.36
13	404	1" Asphalt Concrete, AC-20	CY	869	39.64	34,447.16
14	408	Bituminous Prime Coat	GAL	13,550	0.76	10,298.00
15	608	4" Concrete Sidewalk	SF	49,300	1.77	87,261.00
16	608	Curb Ramp, Type 1 (8 ft. width)	EA	1	55.00	55.00
17	608	Curb Ramp, Type 2 (5 ft. width)	EA	10	51.70	517.00
18	608	Curb Ramp, Type 2 (8 ft. width)	EA	11	69.30	762.30
19	609	Concrete Curb, Type 6	LF	15,031	5.28	79,363.68
20	609	Concrete Curb and Gutter	LF	10	12.00	120.00
21	612	4" Concrete Median	CY	38	143.00	5,434.00
22	SPEC.	Drive Approach (See Plans)	SY	92	28.60	2,631.20

SUBTOTAL - ROADWAY CONSTRUCTION

797,914.00

**CITY OF CENTERVILLE - Clyo Road Extension III
PROJECT DETAIL SHEETS**

Revised February 16, 1993

REF NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
STORM SEWER SYSTEM						
22	601	Rock Channel Protection, Type C w/fabric filter	CY	2	35.00	70.00
23	603	12" Conduit, Type B, ASTM C-76	LF	2,261	15.90	35,949.90
24	603	15" Conduit, Type B, ASTM C-76	LF	940	18.05	16,967.00
25	603	18" Conduit, Type B, ASTM C-76	LF	680	20.50 20.05	13,940.00
26	603	24" Conduit, Type B, ASTM C-76	LF	424	30.00	12,720.00
29	603	48" Conduit, Type B, ASTM C-76	LF	179	68.75	12,306.25
30	604	12" Headwall HW-4	EA	2	250.00	500.00
31	604	48" Headwall HW-4	EA	1	750.00	750.00
32	604	24" Endwall HW-4	EA	3	345.00	1035.00
34	604	Storm Manhole, Type 3	EA	20	1345.00	26,900.00
35	604	Catch Basin, Type 3A	EA	31	795.00	24,645.00
36	604	Catch Basin, Type 3	EA	7	1320.00	9240.00
37	604	Catch Basin, Type 2-2A	EA	1	425.00	425.00
39	604	Connect to existing storm sewer	EA	2	100.00	200.00
40	605	6" Underdrain (707.15 fabric wrapped pipe)	LF	8,314	4.35	36,165.90

SUBTOTAL - STORM SEWER SYSTEM

191,814.05

CITY OF CENTERVILLE - Clyo Road Extension III
PROJECT DETAIL SHEETS
Revised February 16, 1993

REF NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
WATER MAINS						
41	SPEC.	8" D.I. Water Main, Incl. Excavation and Backfill	LF	468	<u>20.90</u>	<u>9781.20</u>
42	SPEC.	12" D.I. Water Main, Incl. Excavation and Backfill	LF	4,056	<u>25.90</u>	<u>105,050.40</u>
43	SPEC.	Remove and Reinstall existing 12" Water Main	LF	125	<u>28.00</u>	<u>3500.00</u>
44	SPEC.	6" Valve	EA	11	<u>310.00</u>	<u>3410.00</u>
45	SPEC.	8" Valve	EA	6	<u>410.00</u>	<u>2460.00</u>
46	SPEC.	12" Valve	EA	6	<u>810.00</u>	<u>4860.00</u>
47	SPEC.	Fire Hydrant	EA	10	<u>900.00</u>	<u>9000.00</u>
48	SPEC.	Relocate Existing Fire Hydrant	EA	1	<u>400.00</u>	<u>400.00</u>
49	SPEC.	12" Tapping Sleeve and Valve	EA	1	<u>5350.00</u>	<u>5350.00</u>
50	SPEC.	Connect to Existing Water Main	EA	4	<u>100.00</u>	<u>400.00</u>

SUBTOTAL - WATER MAINS

144,211.60

REF NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
SANITARY SEWER						
51	SPEC.	8" Sanitary Sewer	LF	113	<u>21.40</u>	<u>2418.20</u>
52	SPEC.	Sanitary Manhole	EA	1	<u>1100.00</u>	<u>1100.00</u>
53	SPEC.	Adjust Existing Manhole to Grade	EA	1	<u>800.00</u>	<u>800.00</u>

SUBTOTAL - SANITARY SEWER

4318.20

**CITY OF CENTERVILLE - Clyo Road Extension III
PROJECT DETAIL SHEETS
Revised February 16, 1993**

REF NO.	ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT COST	TOTAL COST
MISCELLANEOUS						
54	614	Maintaining Traffic	LS	1	5000.00	5000.00
55	619	Field Office	LS	1	500.00	500.00
56	621	Lane Line Striping	MI	2	423.50	847.00
57	621	Channelizing Lines	LF	1,600	0.45	720.00
58	621	Stop Line	LF	85	3.90	331.50
59	621	Crosswalk Lines	LF	180	2.90	522.00
60	623	Construction Staking	LS	1	26,000.00	26,000.00
61	624	Mobilization	LS	1	3,000.00	3,000.00
62	659	4" Topsoil with seed and mulch	SY	8,585	1.00	8,585.00
63	659	Water	MGAL	10	11.00	110.00
64	659	Commercial Fertilizer	TN	1	275.00	275.00
65	713	2" PVC Conduit	LF	1,520	5.00	7,600.00

SUBTOTAL - MISCELLANEOUS

53,490.50

DESCRIPTION	UNIT	TOTAL
GRAND TOTAL		
SUBTOTAL - ROADWAY CONSTRUCTION		797,914.00
SUBTOTAL - STORM SEWER SYSTEM		191,814.05
SUBTOTAL - WATER MAINS		144,211.60
SUBTOTAL - SANITARY SEWER		4,318.20
SUBTOTAL - MISCELLANEOUS		53,490.50

GRAND TOTAL

\$ 1,191,748.35

~~Deduct For Recycled mts - 301 - 275/60~~

~~Deduct For Recycled mts - 402 - 1.00/cy~~

~~to set bid with Alternate~~

No Alternate Proposal
JCR