

RESOLUTION NO. 20-90

CITY OF CENTERVILLE, OHIO

SPONSORED BY COUNCILMAN Mark Bersley ON THE
18th DAY OF June, 1990.

A RESOLUTION ACCEPTING THE BID OF THE TdM
CONSTRUCTION COMPANY FOR 1990 ROAD
IMPROVEMENTS PART TWO FOR THE CITY OF
CENTERVILLE, OHIO, AND TO AUTHORIZE THE
CITY MANAGER TO ENTER INTO A CONTRACT IN
CONNECTION THEREWITH.

WHEREAS, the City advertised for bidders for 1990 Road
Improvements Part Two in the City of Centerville, Ohio, pursuant
to specifications prepared by the City; and

WHEREAS, the TdM Construction Company submitted the low
and best bid.

NOW, THEREFORE, THE MUNICIPALITY OF CENTERVILLE HEREBY
RESOLVES:

SECTION 1. The bid of the TdM Construction Company,
marked Exhibit "A" is hereby accepted, total amount not to exceed
One Hundred Fifty Thousand Dollars (\$150,000.00), and the City
Manager is hereby authorized and directed to enter into any
necessary contract to evidence acceptance of said bid and to make
payment pursuant thereto.

PASSED this 18th day of June,
1990.


Mayor of the City of
Centerville, Ohio

ATTEST:

Mauiel J. McLaughlin
Clerk of the Council of the
City of Centerville, Ohio

CERTIFICATE

The undersigned, Clerk of the Council of the City of Centerville, Ohio, hereby certifies that the foregoing is a true and correct copy of Resolution Number 20-90, passed by the Council of the City of Centerville, Ohio, on the 18th day of June, 1990.

Mauiel J. McLaughlin
Clerk of Council

Approved as to form, consistency
with the Charter and Constitutional Provisions.
Department of Law
Robert N. Farquhar
Municipal Attorney

PROPOSALTo the City of Centerville for the construction of CENTERVILLE - ROAD IMPROVEMENTS 1990 PART II

The signer of this Proposal as bidder declares that he has examined the attached Specifications and Form of Contract, the Advertisement, the Instructions to Bidders, the General Conditions, the Supplemental General Conditions, the Special Conditions, and the Technical Specifications, the Plans and the site of the work, as applicable, and that he will contract to do all the work and furnish all the materials called for by said Plans and Specifications, in the manner and on the conditions required for the following prices, to-wit:

Time Completion: See Bidding Instructions

CENTERVILLE BID

PROPOSAL

Ref. No.	Item No.	Est. Qty.	Description	Unit Price		Total Sum of Material & Labor	Total Price
				Material	Labor		
1.	404	2400 Tons	Asphalt overlay 2" thickness on concrete streets including leveling course; roadside cleanup; eradication of grass and vegetation along curb in streets to be resurfaced (see bidding instruction #17 & specifications)	17.00	5.90	22.90	54,960.00
2.	407	4500 Gal.	Tack coat 0.2 Gal per sq.yd.	0.02	—	0.02	90.00
3.		800 L.F.	Joint on crack repair - milling, with sealing and filling with asphalt concrete; (per detail)	1.30	2.00	3.30	2,640.00
4.		6000 L.F.	Crack sealing (1/2" to 1" wide) and 1" wide and over; (per detail)	0.30	0.17	0.47	2,820.00
5.		12,500 L.F.	Longitudinal and transverse joints - cleaning and sealing including fabric cover; (per detail)	0.75	0.30	1.05	13,125.00

P R O P O S A L

Ref. No.	Item No.	Est. Qty.	Description	Unit Price		Total Sum of Material & Labor	Total Price
				Material	Labor		
6.	604	2 ea.	Adjust Manholes (per detail)	45.00	55.00	100.00	200.00
7.	604	2 ea.	Adjust water valves (per detail)	20.00	30.00	50.00	100.00
8.	202 452	800 Sq. Yds.	Excavate existing 6" concrete pavement to suitable sub-base, dispose defective concrete pavement and replace with 4" of 304 crushed limestone base & 6" of plain Portland cement concrete with integral curb	10.00	23.00	33.00	26,400.00
9.		600 L.F.	Saw cut existing concrete pave- for subsequent removal of defective areas	—	3.00	3.00	1,800.00
10.	310	100 Cu. Yds.	Sub-base excavation & dispose, placing compacted 304 aggregate in place (as directed by Engineer)	16.00	5.00	21.00	2,100.00
11.	604	5 ea.	Minor repair of Type 3 catch basin - replacing apron, one wall and mortar finish with concrete	100.00	250.00	350.00	1,750.00
12.	604	2 ea.	Major repair of Type 3 catch basin - Total Reconstruction (two or more walls to rebuild)	150.00	450.00	600.00	1,200.00

P R O P O S A L

Ref. No.	Item No.	Est. Qty.	Description	Unit Price		Total Sum of Material	Total Price
				Material	Labor		
13.	605 707.15	500 L.F.	Install 4" plastic tile trench underdrain (behind curb in grass area) (per detail)	5.00	7.00	12.00	6,000.00
14.	605 707.15	100 L.F.	Install 4" plastic tile underdrain behind curb under 6" concrete driveways (per detail)	9.00	12.00	21.00	2,100.00
15.	605 707.01	100 L.F.	Install 6" perforated galvanized steel pipe in pavement (per detail)	9.00	12.00	21.00	2,100.00
16.	614	Lump Sum	Maintenance of Traffic	—	2,500.00	2,500.00	2,500.00

GRAND TOTAL (Bid Reference #'s 1 thru 16) **\$ 119,885.00**

Signature Terry Potts

Date JUNE 12, 1990