

RESOLUTION NO. 48-77  
CITY OF CENTERVILLE, OHIO

SPONSORED BY COUNCILMAN Donc Lake ON THE 24th DAY  
OF October, 1977.

A RESOLUTION ACCEPTING PORTIONS OF THE BID OF R. B. & S. CONSTRUCTION COMPANY TO SUPPLY SIDEWALK INSTALLATION AND OTHER IMPROVEMENTS ALONG MAIN STREET/SPRING VALLEY ROAD TO THE CITY OF CENTERVILLE AND TO AUTHORIZE THE CITY MANAGER TO ENTER INTO A CONTRACT IN CONNECTION THEREWITH.

WHEREAS, the City advertised for bidders for sidewalk installation and other improvements along Main Street/Spring Valley Road for the City of Centerville, pursuant to specifications prepared by the City; and

WHEREAS, R. B. & S. Construction Company was the lowest and best bidder;


NOW, THEREFORE, BE IT RESOLVED BY THE MUNICIPALITY OF CENTERVILLE, THAT:

Section 1. The bid of R. B. & S. Construction Company marked Exhibit "A" attached hereto and made a part hereof is hereby accepted, said acceptance being for items 40, 41, 42, 43, 44, 46 and 47, and the City Manager is hereby authorized and directed to enter into any necessary contract to evidence acceptance of said bid and to make payment pursuant thereto.

PASSED this 24th day of October, 1977.

  
\_\_\_\_\_  
Mayor of the City of Centerville, Ohio

ATTEST:

  
\_\_\_\_\_  
Clerk of the Council of the  
City of Centerville, Ohio

CERTIFICATE

The undersigned, Clerk of the Council of the City of Centerville, Ohio, hereby certifies that the foregoing is a true and correct copy of Resolution Number 48-77, passed by the Council of the City of Centerville, Ohio, on the 24th day of October, 1977.

  
\_\_\_\_\_  
Clerk of the Council

Approved as to form, consistency  
with the Charter and Constitutional provisions.

Department of Law  
Robert N. Farquhar  
Municipal Attorney

In case of discrepancy between Unit Prices and Total of Bid based on Estimated Quantities, the Unit Prices will govern.

The above Estimated Quantities are approximate and will be used in the comparison of the bids only. The quantities are not guaranteed and payment will be based on the actual quantities placed or constructed in accordance with the Drawings and Specifications.

The Bidder agrees to complete the work as called for within 35 calendar days after date of commencing operations.

The Bidder acknowledges receipt of Addendum No. \_\_\_\_\_ to this Contract.

If the foregoing Proposal shall be accepted by the City of Centerville and the undersigned shall fail to execute a satisfactory contract, as stated in the Instructions to Bidders, attached hereto, then the Owner may, at their option, determine that the undersigned has abandoned the Contract and thereupon his Proposal shall be null and void and the bond or certified check accompanying this Proposal, or the amount of such check, shall be forfeited to and become the property of the Owner; otherwise, the bond or certified check accompanying this Proposal, or the amount of such check, will be returned to the undersigned.

Attached hereto is a bond or certified check on \_\_\_\_\_  
American Fidelity Ins Co Bank of \_\_\_\_\_  
for the sum of \$ 50,000 bid (\$ \_\_\_\_\_)  
Dollars, in accordance with the terms of the Instructions to Bidders.

The full name and residence of all persons and parties interested in the foregoing bid as principles are as follows:

Name	Address
<u>Wayne Clary</u>	<u>Beesbrook Pa</u>
<u>Ray Clary</u>	<u>Harrisburg Pa</u>
<u>Robert Morgan</u>	<u>Lynchburg Pa</u>
<u>Tom Seiber</u>	<u>Fairborn Pa</u>

Signature of Bidder RB & S Const. Co  
W. A. Clark - Partner

Business Address of Bidder 241 W. Main St. Chillicothe, Mo.

Dated at Centerville Ohio

the 26 day of Aug, 1977.

The Bidder is required to state in detail below what work of a character similar to that included in the proposed Contract he has done and to give references and such other information as will enable the Owner to judge of his responsibility, experience, skill, business and financial standing.

EXPERIENCE STATEMENT

Similar Work for

City of Dayton - City of Springfield - County of Warren

County of Montgomery - City of Xenia and other

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

# PROPOSAL

REF. NO.	ITEM NO.	EST. QTY.	DESCRIPTION	UNIT	PRICE	TOTAL (SUM OF MATERIAL AND LABOR)	TOTAL PRICE
				MATERIAL	LABOR		
8	--	30 sq. yds.	Resod disturbed areas adjacent to widening	.75	1.25	2.00	60.00 <i>Twenty dollars</i>
9		3	Install 6" protector posts	25.00	25.00	50.00	150.00 <i>One hundred fifty dollars</i>
<u>CORRECT BLACKTOP AREAS NORTH &amp; SOUTH OF SPRING VALLEY ROAD, WEST OF MAIN STREET</u>							
10	403	70 sq. yds.	Asphalt leveling course 2" ±	1.75	1.75	3.50	245.00 <i>Two hundred forty five dollars</i>
11	404	70 sq. yds.	Asphalt surface course 2" ±	1.75	1.75	3.50	245.00 <i>Two hundred forty five dollars</i>
12	--	2	Replace and adjust (2) catch basins	200.00	200.00	400.00	800.00 <i>Eight hundred dollars</i>
13	--	--	Miscellaneous, relating to turn lanes and correction of catch basins	50.00	450.00	500.00	500.00 <i>Five hundred dollars</i>
			(Items with Reference No. 1 thru 13) TOTAL				2450.00 <i>Eight thousand eight hundred ten dollars</i>
<u>INSTALL BLACKTOP SIDEWALK</u>							
14	201 & 203	1110 lin. ft.	Subgrade preparation for 3' wide blacktop walk	0	.50	.50	550.00 <i>Five hundred fifty five dollars</i>
15	304	1110 lin. ft.	6" gravel base for 3' wide blacktop walk	1.00	.50	1.50	1665.00 <i>One thousand six hundred sixty five dollars</i>

PROPOSAL

To the City of Centerville for the construction of Sidewalk and Other Improvements Main Street/Spring Valley Road

The signer of this Proposal as bidder declares that he has examined the annexed Specifications and Form of Contract, the Advertisement, the Instructions to Bidders, the General Conditions, the Supplemental General Conditions, the Special Conditions, and the Technical Specifications, the Plans and the site of the work, as applicable, and that he will contract to do all the work and furnish all the materials, called for by said Plans and Specifications, in the manner and on the conditions required for the following prices, to-wit:

PROPOSAL

REF NO.	ITEM NO.	EST. QUANT'Y	DESCRIPTION	UNIT PRICE		TOTAL (SUM OF MATERIAL AND LABOR)	TOTAL PRICE
				MATERIAL	LABOR		
<u>INSTALLATION OF BLACKTOP TURN LANES. WIDENING AT CROSSWALK (SPRING VALLEY ROAD)</u>							
1	201 & 203	500 sq. yds.	Subgrade Preparation (including removal of 2 driveways) Aggregate base	0	2.00	2.00	1000.00 <i>One thousand dollars</i>
2	304	500 sq. yds.	Aggregate Base (2) 5" courses	2.00	2.00	4.00	2000.00 <i>two thousand dollars</i>
3	408	100 gal.	Prime coat	.50	1.00	1.50	150.00 <i>One hundred fifty dollars</i>
4	403	560 sq. yds.	Asphalt leveling course, 1½"	1.40	1.60	3.00	1680.00 <i>One thousand six hundred eighty dollars</i>
5	404	560 sq. yds.	Asphalt surface course, 1½"	1.40	1.60	3.00	1680.00 <i>One thousand six hundred eighty dollars</i>
6	--	10 lin. ft.	Installation of 12" storm tile (Sta. 2+00, Main Street)	5.00	10.00	15.00	150.00 <i>One hundred fifty dollars</i>
7	--	30 sq. yds.	Adjust area adjacent to turn lane(s) Install 2' gravel berm, as shown on plans	2.00	3.00	5.00	150.00 <i>One hundred fifty dollars</i>

# PROPOSAL

REF. NO.	ITEM NO.	EST. QTY.	DESCRIPTION	UNIT		TOTAL (SUM OF MATERIAL AND LABOR)	TOTAL PRICE
				MATERIAL	LABOR		
16	404	1110 lin. ft.	3" blacktop surface course (in two lifts) for 3' wide blacktop walk	1.25	1.75	3.00	Three thousand three hundred thirty dollars 3330.00
17	--	16 lin. ft.	15" concrete drain tile (Sta. 12+70, Main Street)	1.50	12.50	20.00	Three hundred twenty dollars 320.00
18	--	Lump Sum	Crossing at creek of creek (Sta. 15+20, Main Street)	160.00	400.00	500.00	Five hundred dollars 500.00
19	--	50 sq. yds.	Adjusting of areas adjacent to sidewalk	0	2.00	2.00	One hundred dollars 100.00
20	--	Lump Sum	Miscellaneous, relating to blacktop sidewalk	50.00	450.00	500.00	Five hundred dollars \$ 500.00
			(Items with Reference No. 14 thru 20) TOTAL				six thousand six hundred seventy dollars 6470.00

## INSTALL CONCRETE SIDEWALK

21	201 & 203	650 lin. ft. (5' wide)	Subgrade preparation	0	1.00	1.00	One hundred fifty dollars 650.00
22	304	650 lin. ft. (5' wide)	Gravel base 4"	.50	.50	1.00	One hundred fifty dollars 650.00

# PROPOSAL

IF O.	ITEM NO.	EST. QTY.	DESCRIPTION	UNIT		TOTAL (SUM OF MATERIAL AND LABOR)	TOTAL PRICE
				MATERIAL	LABOR		
13	--	650 lin. ft. (5' wide)	Concrete sidewalk 4" thick	1.50	3.50	5,100	One thousand two hundred fifty dollars 3250.00
14		see plan	Painting of crosswalks, edge lines, etc., at Clareridge Lane and Spring Valley, also from 9+00 to 12+00, Spring Valley Rd.	200.00	800.00	1,000.00	One thousand dollars 1000.00
15		200 ea.	Installation of "Simsonite" (or equal) Reflectors at crosswalks	2.50	.50	3,000	two hundred dollars 600.00
16		1 ea.	Pedestrian center island (see plan)	100.00	400.00	500.00	five hundred dollars 500.00
17		2 ea.	Advance warning signs	50.00	50.00	100.00	two hundred dollars 200.00
18		2 ea.	Pedestrian crossing signs	50.00	50.00	100.00	two hundred dollars 200.00
19		2 ea.	Pedestrian island signs	50.00	50.00	100.00	two hundred dollars 200.00
30		2 ea.	Remove curb and install curb ramp (Sta. 10+70, Spring Valley Rd.)	75.00	175.00	250.00	five hundred dollars 500.00
31		18 lin.ft.	New curb on Clareridge Lane	2.40	3.00	5.00	ninety dollars 90.00
32		2	Remove and replant decorative trees (4" dia. +)	0	200.00	200.00	four hundred dollars 400.00
33		100 sq. yds.	Adjust grade adjacent to sidewalk, apply 4" topsoil, resod.	1.00	1.00	2.00	two hundred dollars 200.00

# PROPOSAL

EF NO.	ITEM NO.	EST. QTY.	DESCRIPTION	UNIT	PRICE	TOTAL (SUM OF MATERIAL AND LABOR)	TOTAL PRICE
				MATERIAL	LABOR		
34		16 lin.ft.	Install 12" drain tile (Sta. 9+10 Spring Valley Rd.)	5.00	7.00	14.00	142.00 <i>One hundred and twenty two dollars</i>
35		1 ea.	Install catch basin, Neenah # R-4360 or equal (Sta. 9+10 Spring Valley Rd.)	150.00	250.00	400.00	400.00 <i>Four hundred dollars</i>
36		1 ea.	Adjust catch basin (Sta. 9+10 Spring Valley Rd.)	50.00	50.00	100.00	100.00 <i>One hundred dollars</i>
37		10 lin.ft.	12" concrete drain tile (Spring Valley Road, Sta. 10+50)	5.00	7.00	12.00	120.00 <i>One hundred twenty dollars</i>
38		Lump Sum	Setting of grade stakes. All engineering and surveying work responsibility of contractor.	50.00	450.00	500.00	500.00 <i>Five hundred dollars</i>
39		Lump Sum	Miscellaneous, relating to sidewalk installation (for instance adjusting of drains, adjusting of grade, etc.)	100.00	900.00	1000.00	1000.00 <i>One thousand dollars</i>
			(Items with Reference No. 21 thru 39)	TOTAL			10752.00 <i>ten thousand seven hundred fifty two dollars</i>



# PROPOSAL

ITEM NO.	EST. QTY.	DESCRIPTION	UNIT	PRICE	TOTAL (SUM OF MATERIAL AND LABOR)	TOTAL PRICE
			MATERIAL	LABOR		
<u>INSTALL CONCRETE STORM SEWER</u>						
	400	24" concrete storm sewer (including lin. ft. base preparation)	10.00	10.00	400.00	8000.00 <i>eight thousand dollars</i>
	4	Precast concrete manholes (open top gratings)	300.00	200.00	500.00	2000.00 <i>two thousand dollars</i>
	2	catch basins	200.00	200.00	400.00	800.00 <i>eight hundred dollars</i>
	6 sq. yds.	Concrete apron (Spring Valley Rd. Sta. 3+00)	20.00	20.00	120.00	120.00 <i>One hundred twenty dollars</i>
	10 cu. yds.	Rip-Rap (channel protection) Spring Valley Rd. Sta. 3+00 and Sta. 8+65	8.00	12.00	20.00	200.00 <i>two hundred dollars</i>
	Lump Sum	Setting of grade stakes or alignment stakes (All eng. stakes by contractor)	50.00	450.00	500.00	500.00 <i>Five hundred dollars</i>
	150 cu. yds.	Backfill and regrading of existing ditch (at least 4" topsoil required)	1.50	2.50	4.00	600.00 <i>six hundred dollars</i>
	150 sq. yds.	Resodding of disturbed areas	.75	.75	1.50	225.00 <i>two hundred twenty five dollars</i>
	5 ft.	Extend existing culvert, include excavation for footer (Spring Valley, Sta. 8+60)	50.00	150.00	200.00	1000.00 <i>one thousand dollars</i>
	140 lin. ft.	Widen Berm (Spring Valley in vicinity of culvert)	3.00	5.00	6.00	840.00 <i>eight hundred forty dollars</i>

# PROPOSAL

F. I.	ITEM NO.	EST. QTY.	DESCRIPTION	UNIT PRICE		TOTAL (SUM OF MATERIAL AND LABOR)	TOTAL PRICE
				MATERIAL	LABOR		
0		145 sq. yds.	4' blacktop overlay in two lifts	3.00	3.00	6.00	\$ 70.00 <i>eight hundred seventy dollars</i>
1		16 lin. ft.	Steel guard rail	12.00	8.00	20.00	320.00 <i>three hundred twenty dollars</i>
2		20 ea.	Simsonite Reflectors	2.50	.50	3.00	60.00 <i>sixty dollars</i>
3		300 lin. ft.	Repaint & stripe and edge of blacktop roadway at places where new blacktop was applied	.50	1.00	1.50	450.00 <i>four hundred fifty dollars</i>
4		30 lin. ft.	Clean out and reshape existing ditch	0	5.00	5.00	150.00 <i>one hundred fifty dollars</i>
5		16 lin. ft.	Install split rail fence, Spring Valley Sta. 5+95	3.00	7.00	10.00	160.00 <i>one hundred sixty dollars</i>
6		Lump Sum	Miscellaneous, relocate fences and just grade in vicinity of improvements, etc.	100.00	700.00	800.00	\$ 800.00 <i>eight hundred dollars</i>
			(Items with Reference No. 40-56)	TOTAL			<i>fifteen thousand</i> 17095.00 <i>ninety five dollars</i>
NOTE: If bidder is submitting a Quotation for the entire project give a grand total for all items from 1 thru 56.							<i>forty three thousand six hundred twenty seven dollars</i> 43 627.00
<u>GRAND TOTAL</u>							<i>twenty seven dollars</i>