

## **Item C202 – Curb, Curb Ramp, Sidewalk, Bikepath, Pavement and Driveway Removed**

### **C202.1 Description**

### **C202.2 Method of Measurement**

### **C202.3 Basis of Payment**

**C202.1 Description.** This item shall consist of the removal and disposal of curb, combined curb and gutter, integral curb, curb ramp, sidewalk, bikepath, pavement, driveway of the thickness specified at the location indicated or as directed by the City Engineer. This item shall also include the removal of up to 4 inches of base material under concrete or pavement, or up to 6 inches if under a bikepath.

Areas of designated removal shall be sawed square and even. Saw cutting shall be full depth. Any damage and removal beyond the specified removal area shall be removed and restored at the contractor's expense, unless otherwise approved by the City Engineer. Any reinforcing bars or mesh encountered shall be removed. The reinforcing that remains shall be sawed flush with the existing concrete.

Brick pavers shall be removed with care for future re-use on project or delivered to the Public Works Center at 7970 South Suburban Road for storage.

When an asphalt driveway apron is replaced with a concrete driveway apron, a 2' wide strip of the asphalt drive shall be removed and replaced behind the apron after the concrete pour. This 2' wide strip shall comply with and be paid under Item 448 Asphalt Driveways. See Item C448 Asphalt Concrete for restoration requirements. Concrete driveways shall not be disturbed unless directed by the City Engineer.

**C202.2 Method of Measurement.** The quantity of sidewalk, curb ramp, driveway, and pavement to be paid for will be the actual number of square feet of driveway, sidewalk and curb ramp removed and disposed of, as directed.

The quantity of bikepath and pavement to be paid for will be the actual number of square yards of bikepath and pavement removed and disposed of, as directed.

The quantity of curb and/or combined curb and gutter to be paid for will be the actual number of lineal feet of curb and necessary pavement (up to 42-inches measured from the back of curb) removed and disposed of as directed.

The quantity of integral curb (concrete panel streets) to be paid for will be the actual number of lineal feet of curb and necessary pavement (up to 30-inches measured from the back of curb) removed and disposed of as directed.

The quantity of reinforcing bars or mesh to be removed will be included with the respective item. All necessary sawing for the removal shall be incidental to the work. No separate payment will be made for this item.

**C202.3 Basis of Payment.** The price bid for this item shall include all labor, equipment and material necessary for the removal of the sidewalk, bikepath, curb ramp, pavement with integral curbs, curbs, combined curb and gutter, integral curbs, pavement and driveways, including necessary base material removal, excavation, sawing and removal of reinforcing and as directed by the Engineer.

Payment will be based on the unit price bid:

<b>Item</b>	<b>Unit</b>	<b>Description</b>
C202	Square Foot	Concrete Sidewalk Removed
C202	Square Foot	Brick Sidewalk Removed (with aggregate base)
C202	Square Foot	Brick Sidewalk Removed (with concrete base)
C202	Square Foot	Curb Ramp Removed
C202	Square Foot	Asphalt Driveway Removed
C202	Square Foot	Concrete Driveway Removed, __”
C202	Square Yard	Pavement Removed, __”
C202	Linear Foot	Curb Removed
C202	Square Yard	Bikepath Removed, Asphalt, __”