

## Item C202 - Removal of Concrete Pavement

- C202.1 Description**
- C202.2 Method of Measurement**
- C202.3 Basis of Payment**

**C202.1 Description.** This item shall consist of the removal and disposal of concrete pavement with or without integral curbs, curbs and integral curbs. This item shall also include the removal of up to 4 inches of base material under the concrete pavement item.

The edges of concrete to be left in place shall be sawed square and even. Any reinforcing bars or mesh encountered shall be removed. The reinforcing that remains shall be sawed flush with the existing concrete. The curb removed work item shall include adjacent full-depth pavement removal up to the limits of the saw cut line. This work shall be incidental to the curb removed item.

**C202.2 Method of Measurement.** The quantity of concrete pavement including integral curb to be paid for shall be the actual number of square yards, of the nominal thickness stipulated, removed and disposed of as directed. Where the thickness in an area is not reasonably uniform, the average thickness of the concrete removed shall be used to determine the nominal thickness.

The quantity of curb to be paid for will be the actual number of linear feet removed and disposed of as directed.

The quantity of integral curb to be paid for will be the actual number of linear feet of curb and necessary pavement (up to 30-inches measured from the back of curb) removed and disposed of as directed.

The quantity of reinforcing bars or mesh to be removed will be included with the respective item. No separate payment will be made for this item.

**C202.3 Basis of Payment.** The price bid for this item shall include all labor, equipment and material necessary for the removal of the sidewalks, pavement with integral curbs, curbs, combined curb and gutter, integral curbs and driveways, including necessary base material removal, sawing and removal of reinforcing and as directed by the Engineer.

Payment will be based on the unit price bid:

<b>Item</b>	<b>Unit</b>	<b>Description</b>
C202	Linear Feet	Curb Removed
C202	Square Yards	Concrete Pavement Removed